

# LAFORCE



## WHAT IS PRE-INSTALLATION?

The process in which hardware such as hinges, door closers, exit devices, locks, electrified hardware, and flat goods are installed onto the doors prior to shipping to the jobsite.

## BENEFITS OF PRE-INSTALLATION

- Lowers costs and installation time at the jobsite
- Allows doors to be delivered closer to the actual installation deadline, which reduces the potential for on-site damage
- Allows LaForce to catch manufacturing or product defects and fix it prior to delivering materials
- Contributes to lean construction practices
- Hardware is applied by trained hardware installers in a controlled environment - no more on-site guesswork

### ✓ ITEMS LAFORCE **DOES** PRE-INSTALL

- All Wiring within the Hardware/Doors
- Electric Locksets
- Hinges
- Locksets
- Closers
- Flushbolts
- Kickplates
- Overhead Stops
- **Electrified Hardware:**
  - Exit Devices
  - Electric Strikes
  - Programmable Locks
  - Special Applications
  - Accessories

### ✗ ITEMS LAFORCE DOES **NOT** PRE-INSTALL

- Wiring within Frames (ie. electric strikes)
- Strike Plates
- Wall Stops
- Pivots
- Coordinators
- Concealed Closers
- Cylinders/Cores
- Weatherstripping/Sweeps/Auto Door Bottoms
- Astragals
- Thresholds
- Magnetic Hold Opens
- Power Supplies
- Screws, Strike Plates, etc. (Bag taped to door)

## PRE-INSTALLATION PROCESS AT LAFORCE



Hardware installed



Electrified hardware tested



Packaged with spacers and corner guards



Shipped to jobsite and ready for you to install